Cambridge Instruments
& Engg. Co.

EST. 1963 · HOWRAH, INDIA

INSULATION TESTER · MOTOR-OPERATED

# CIE/777

## 5000 V · 100–100000 MΩ

Motorised insulation tester · sustained PI / DAR · guard terminal

## 01 KEY FEATURES

- Mains-motor driven
- Sustained PI & DAR testing
- Guard terminal & infinity adjuster
- Seasoned wooden body, detachable lid & lock




CIE/777 · INSULATION TESTER · REPRESENTATIVE IMAGE

## 02 TECHNICAL SPECIFICATIONS

| PARAMETER | SPECIFICATION |
|---|---|
| **CONFIGURATION** | |
| Rated Test Voltage | 5000 V D.C. |
| Insulation Resistance Range | 100–100000 MΩ |
| **DRIVE & MEASUREMENT** | |
| Drive | Mains motor, 230 V, 50 Hz A.C. |
| Scale Length | 100 mm (approx.) |
| Accuracy | As per IS: 2992-1987 |
| Response Time | 3 seconds |
| Guard Terminal & Infinity Adjuster | Guard ring & guard terminal eliminate surface-leakage errors; infinity adjuster provided |
| **TEST & SAFETY** | |
| High Voltage Test | Min. 2kV or (rated V + 1)kV A.C. r.m.s., 1 min |
| Insulation Resistance Test | Better than 50 MΩ at 500V D.C. |
| **GENERAL** | |
| Body | Seasoned wooden cabinet, sunmica finish, detachable lid, handle, lock |
| Dimensions (top cover) | 14 × 10 × 10 inch (approx.) |
| Weight (top cover) | 9 kg (approx.) |
| Warranty | 12 months against manufacturing defects only |

*Dual-voltage, dual-range options and custom ranges are available against specific requirements - enquire.*

## 03 APPLICATIONS

- Sustained PI testing on large motors and generators
- Power transformer insulation & DAR assessment
- HV cable and switchgear insulation testing
- Substation commissioning by EPC contractors

## 04 WHAT'S IN THE BOX

✓ Mains cord, 2 metres ✓ 1 pair of H.V. testing leads

## 05 OPTIONAL ACCESSORIES

+ Rexine carrying case
+ 15-minute timer facility
+ Additional/special H.V. leads, 2m
+ Dual voltage & range option
+ Single voltage, dual range option



All specifications are subject to change without prior notice. © Cambridge Instruments & Engg. Co. - CIE/777 5000 V, 100-100000 MΩ Product Catalogue.